

**ADDENDUM NO. 3
FOR
PROGRAM C WELL WATER TRANSMISSION MAIN**

DATE: March 27, 2023

FROM: Wallace Group
612 Clarion Court
San Luis Obispo, CA 93401
Tel: (805) 544-4011

TO: Prospective Bidders

This addendum forms a part of the Contract Documents and modifies the original Procurement Documents dated February 2023, and Addendums 1 and 2, as noted herein. Each bidder shall acknowledge receipt of this Addendum by completing the acknowledgment at the end of this Addendum, and by confirming receipt of this addendum on the contract Bid Form. Failure to do so may subject Bidder to disqualification.

The following changes or clarifications have been made to the Bid Documents:

CHANGES TO PRIOR ADDENDA:

1. None.

CHANGES TO PROCUREMENT REQUIREMENTS:

2. Bid Schedule. Replace the Bid Schedule with the attached revised Bid Schedule.

CHANGES TO CONTRACTING REQUIREMENTS:

3. None.

CHANGES TO SPECIFICATIONS:

4. Section 010000, General Requirements. Contractor's attention is directed to Paragraph 3.02 Protection of Work and Property. Traffic loops must be replaced entirely; no splicing is allowed. Contractor's attention is also directed to Drawing D-5 note "L" of the "A3: Traffic Control Notes". Traffic loops must be replaced within 5-days and the Contractor shall install temporary video detection system(s) at the intersection which are acceptable to the County of San Luis Obispo, for the duration that such traffic loops are out of service.
5. Section 012000, Price and Payment Procedures. To Paragraph 1.04 Bid Items, Add Bid Item 13 as follows:
 - "N. Bid Item No. 13 – Replace Traffic Loops
 1. Measurement
 - a. Measurement for Bid Item No. 13 shall be based on completion of such work on a lump sum basis.
 2. Payment

a. Payment for Bid Item No. 13 shall be made on a lump sum basis upon successful completion of the work and satisfactory inspection by the County of San Luis Obispo. The lump sum cost shall constitute full compensation for furnishing all labor, materials, tools, and equipment associated with performing all of the work to remove and restore in compliance with the County of San Luis Obispo standards. Work performed under this bid item shall be performed in accordance with said standards and shall follow note "L" of the "A3: Traffic Control Notes" located on drawing D-5. Contractor shall provide temporary video detection system(s) satisfactory to the County of San Luis Obispo. No splicing shall be allowed."

Item L. Bid Item No. 11, Pavement Repair-Hot Mix Asphalt, is clarified as follows:
"Bidders shall assume an average pavement restoration depth of 8 inches, with a modified estimate of hot mix asphalt of 738 tons. This is now reflected in the revised bid schedule."

6. Section 015000, Temporary Facilities and Controls. Paragraph 1.07 Traffic Regulation. Add the following: "Refer to Appendix A, Pending San Luis Obispo County Encroachment Permit."
7. Section 015000, Temporary Facilities and Controls. Paragraph 1.09.B.2, Tree Roots, add the following: "When Oak Tree roots are encountered, notify Engineer immediately of such encounters, and do not cut through any Oak Tree roots without prior approval of the Engineer and Owner."
8. Section 31 23 17, Paragraph 2.01. Add the following clarification to Paragraph 2.01.A: "Contractor shall use imported sand bedding in the pipe zone per this Section/Paragraph." Add the following clarification to Paragraph 2.01.B: " Use either recycled native material or imported material meeting Soil Type S1 or S2 as specified in Section 31 05 13, Soils for Earthwork. Beneath pavement (both County streets and driveways) Contractor shall refer to detail U-4 and is permitted to use the following in the trench zone: aggregate material compacted to 95% relative compaction conforming to Section 31 05 16 or a sand cement slurry conforming to the County trench detail."
9. Appendix A, Pending San Luis Obispo County Encroachment Permit. With respect to traffic control through the Los Osos Valley Road/South Bay Boulevard intersection, lane closures are allowable with a County-approved traffic control plan. Night Work is allowable with advanced approval by the County and the District (road closures are still not allowable), and as approved as part of the Traffic Control Plan .

CHANGES TO DRAWINGS:

10. None.

CLARIFICATIONS:

11. Ductile iron pipe called for on the plans shall be included in the unit price per lineal foot for Bid Item No. 5, 8-inch Polyvinyl Chloride (PVC) Water Transmission Main.

Please acknowledge receipt of this Addendum No. 3 by signing where indicated below. **Please email a PDF copy of this signed addendum to stevent@wallacegroup.us.**

Company Name

Date

END OF ADDENDUM

BID SCHEDULE

**LOS OSOS COMMUNITY SERVICES DISTRICT
PROGRAM C WELL WATER TRANSMISSION MAIN**

Refer to Section 01 20 00, Price and Payment Procedures, for further definitions of the bid items in this Bid Schedule.

| Item No. | Est. Qty | Unit | Description | Unit Price | Total Price |
|-----------------------|----------|------|--|------------|-------------|
| 1 | 1 | LS | Mobilization and General Conditions | | |
| 2 | 1 | LS | Sheeting, Shoring, and Bracing | | |
| 3 | 1 | LS | Traffic Control | | |
| 4 | 1 | LS | Protection of Utilities | | |
| 5 | 3269 | FT | 8-inch Polyvinyl Chloride (PVC) Water Transmission Main | | |
| 6 | 9 | EA | 8-inch Gate Valve | | |
| 7 | 1 | EA | 2-inch Combination Air-Vacuum Release Valves | | |
| 8 | 3 | EA | 2-inch Blow Off | | |
| 9 | 1 | LS | Tie-in Location | | |
| 10 | 1 | LS | Testing and Disinfection | | |
| 11 | 738 | TON | Pavement Repair – Hot Mix Asphalt | | |
| 12 | 225 | CY | Pavement Repair – Class 2 Aggregate Base | | |
| 13 | 1 | LS | Replace Traffic Loops | | |
| TOTAL BASE BID | | | | | \$ |

Total Bid Amount in Words: _____

Signature of Bidder: _____ Date: _____

The undersigned agrees to perform, for the benefit of the OWNER, the work itemized herein, and in accordance with all San Luis Obispo County, State, and Federal laws.

All materials and equipment used in the execution of the described work shall comply with all applicable State and Federal codes, regulations and requirements.

The Contractor shall verify all measurements and submit a unit price for the facilities shown above. Payment will be made on a unit price basis.